MYSORE DIVISION.

Notification dated 9th January 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12 noon on 28th January 1933, for Restoring Rudrakshipur Tank, Reg. No. 213, Mandya Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Rudrakshipur Tank, Reg. No. 213, Mandya Taluk in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitior will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates should be quoted for each item of work and no lump sum quotation will be accepted.

Abstract estimate for Restoring Rudrakshipur Tank, Regd. No. 213, Mandya Taluk—

No.	Items of work	Quantity	Per	Rate	
				In figures	In words
	I Bund.				
1	Earth work including watering and tamping after picking the surface.	9,551	C.yd.		
2	Cutting grips for seat of new bund ...	Lump	sum		
3	Turfing the slopes	908·00	Sqr.		
4	Removing and refixing available grade stones including cutting figures and painting.	4	Each		
5	Preparing and fixing new grade stones including figuring and painting.	34	"		
6	Providing and fixing new index stones ...	38	"		
7	Providing Regd. No. and date stone including cutting figure and painting.	1	"		
8	Removing jungle	Lump	sum		
9	Fixing new gauge stone	1	Each		
	II Sluice.				
1	Cut open the bund examining and repairing the existing sluice and refilling.	Lump	sum		
2	Providing new plug rod and locking arrangements.	Lump	sum		
	III Left Waste Weir.				
1	Removing and carrying the available stones from the right weir to left weir.	8	C.yd.		
2	Earth work excavation	93	"		
3	Stone jelly concrete in surki mortar ...	488	C.ft.		
4	Burnt Brick in surki mortar	337	"		
5	Stone slabs, 6" thick, top and sides dressed...	288	S.ft.		
		6·05	Sqr.		

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 11th January 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Excutive Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 3 P.M., on 1st February 1933, for laying Underground Sub-main Sewer No. 2 from the Central Jail Extension to the flood water main drain in Sultanpet, *via* Balepet, Bangalore City". An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Sanitary Engineer's Office, between the hours of 11 A.M. to 5 P.M. on all Office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for laying Underground Sub-main Sewer No. 2, from the Central Jail Extension to the flood water main drain in Sultanpet, *via* Balepet, Bangalore City," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind; the decision of the Executive Sanitary Engineer will be final and legally binding.

Abstract Estimate of quantities of work to be done for Laying Underground Sub-main Sewer No. 2, from the Central Jail Extension to the flood water main drain in Sultanpet *via* Balepet, Bangalore City.

	Particulars	Unit	Quantity
I.	Earthwork excavation for trenches for laying the pipe line, including refilling trenches in layers of 1' watering and tamping to restore the surface to original ground level and forming sides, including cost of barricading and lighting and keeping watch for preventing accidents either by day or night, the contractor being responsible for any accident and restoring the surface of filled up trench in case of settlement. The excavation should be correct to levels and gradient given and in any case of extra depth excavated beyond this the contractor will restore the surface to correct level by filling up with surki concrete at his own cost.		
	(i) Gravelly soil	C.yds.	2,270
	(ii) Soft rock	"	757
II.	Laying and jointing stoneware pipes with 1 to 1 cement mortar with necessary yarn caulking and finishing the joint including the cost of stoneware pipes of approved quality with perfect glaze and absolutely straight and without any flaw in the make and including all charges of testing the pipe line before the closing of the trench for pipes of sizes as in following :—		
	9" Diameter	R.ft.	1,248
	12" do	"	2,532

Particulars	Unit	Quantity
The pipe line will be kept open for the inspection of each joint by the Executive Sanitary Engineer or his representative and will not be closed without his permission.		
III. Constructing manholes of 4 ft. diameter including earthwork, excavation, correct to the required dimension, cement concrete bed of one foot depth and 6¾ ft. diameter, side walls of 1 1/8 foot thick of brick in cement mortar 1 to 5, if necessary taper for fixing the manhole frame including the cost of cast iron heavy manhole cover and frame of 4 Cwt. and of design to be seen at the office and necessary number of cast iron steps of the standard design, making drains with cement concrete and cement plaster, 3/4 of the depth of the pipe drain joining it and with 4" slope from side walls to drain and cement plastering ½" thick inside the manhole all over with 1 to 3 cement mortar, etc., complete of depths as in the following :—		
Upto 4 ft. depth	No.	12
4′ to 5′ depth	„	5
6′ to 7′ „	„	2
7′ to 8′ „	„	4
8′ to 9′ „	„	3
9′ to 10′ „	„	2
10′ to 11′ „	„	2
IV. Providing house connections including the cost of stoneware P trap of 4" with cast iron grating and 4" dia. stoneware pipes and junction pipes on sub-main line, if necessary, and constructing of cisterns cast iron silt catcher bucket and rain water separating arrangement as per design complete.	„	200
V. Constructing flushing tank with masonry of capacity to contain 200 gallons of water and construction as per manholes including cost of flushing syphon of suitable size.	„	5
VI. Constructing ventilating shafts with 4" boiler tube of 16 ft. high masonry support including cement plastering to it and cost of cast iron bend and pipes up to manhole and fixing complete.	„	1
VII. Carting surplus earth and clearing site and forming, etc., complete.	Cyd.	757

B. R. GARUDACHAR,
Executive Sanitary Engineer,
Bureau of Sanitary Engineering.

DEPARTMENT OF AGRICULTURE.

OFFICE OF THE MANAGER, GOVERNMENT EXPERIMENTAL FARM, HIRIYUR.

Notification dated 28th November 1932.

Sealed tenders will be received in the Office of the Manager, Government Experimental Farm, Hiriyur, up to 4 P.M., on 23rd January 1933, for executing the undermentioned items of work in connection with the Jaggory boiling, which will begin by about the last week of January 1933.

1. Tenders should be superscribed "Tender for work in connection with Jaggory boiling in Babbur Farm" and should be accompanied with a deposit of Rs. 100 as earnert money.

2. The quantity of work shown is approximate and cannot be guaranteed.

3. Tenders will be opened at 4 P.M. on Monday the 23rd January 1933 in the presence of as many tenderers as are present at that time and the name of successful tender will be notified within two weeks. The deposits of the unsuccessful tenderers will then be returned to them.

4. The undersigned reserves to himself the right to accept any tender and to rejec the (lowest) or any tender without assigning any reason whatsoever therefor.